


SHEET NOTES

1. VFD MOUNTED IN MAIN CONTROL PANEL.
2. TEMPERATURE CONTROLLED BY TIC CONTROLLER.
3. SPENCER VALVE CONNECTION.
4. COMPRESSED AIR FOR VAC-U-MAX RECEIVER AND COMIL (IF NEEDED) WILL BE SUPPLIED FROM POST HOIST SUPPORT ARMS.
5. SUPPLY FAN CONTROLLED VIA PRESSURE TRANSMITTER TO ENSURE FAN IS OPERATING WITHIN GREEN ZONE.
6. DRIP TRAY.
7. BLEED SCREENS: BLEED OFF 10% TOTAL AIR VOLUME.
8. CONDENSATE GENERATED FROM COOLING COILS TO BE ROUTED TO FLOOR DRAIN. REFER TO PLUMBING DRAWINGS FOR DRAINAGE ROUTING.
9. VACUUM PUMP TO BE LOCATED IN NEARBY MECHANICAL SPACE. REFER TO GENERAL ARRANGEMENT PLANS FOR LOCATIONS.
10. VALVE TO AUTOMATICALLY SHUT OFF ON LOW O2 ALARM.
11. DUST COLLECTION DROP EQUIPPED WITH SNORKEL CONNECTION.
12. SPEC TRANSITION TO OCCUR IN DOWNFLOW BOOTH INTERSTITIAL SPACE.

PROJECT LOCATION

6701 EVANSTAD DR N
MAPLE GROVE, MN 55369



KEYPLAN

CLIENT

UPSHER-SMITH

Partners in Health Since 1919

CONSULTING ENGINEER

HORWITZ

7400 49th AVENUE NORTH
NEW HOPE, MN 55428
(763) 533-1900
www.horwitzinc.com

PROJECT TITLE

PROJECT KEYSTONE - PHASE 1

REV	BY	DATE	AS RECORDED	DESCRIPTION
0	RS	05/25/22		

LICENSEE

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Date **05/25/22** LIC NO _____

CONFIDENTIAL - THIS DRAWING IS THE PROPERTY OF UPSHER-SMITH. THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE OWNER.

PROJ. NO.	2022.1720	DESIGNED BY:	Designer
SCALE:	1/2" = 1'-0"	CHECKED BY:	Checker
SHEET SIZE:	30x42	APPROVED BY:	Approver

DRAWING TITLE

WEIGHING/DISPENSING ROOM 1650

DRAWING NUMBER

PID-1010